

January 26, 2007

**ADDENDUM NO. 4
TO
THE PLANS AND SPECIFICATIONS
FOR
SENTER ROAD WIDENING PROJECT – PHASE II
(TULLY ROAD TO SINGLETON ROAD)**

Notice is hereby given that the following revisions, additions and/or deletions are hereby made part of, and incorporated into the Plans and Specifications for the Senter Road Widening Project – Phase II (Tully Road to Singleton Road).

IMPORTANT

THIS ADDENDUM SHOULD BE ACKNOWLEDGED WHEN YOUR BID IS SUBMITTED. FAILURE TO ACKNOWLEDGE THE ADDENDUM MAY CONSTITUTE GROUNDS FOR REJECTION OF THE BID.


INSTRUCTIONS:

The bidder must sign this addendum in the space provided below and return one signed copy with the bid. Failure to return the signed copy with the bid document shall not relieve the bidder of his/her obligation to include this addendum in the bid proposal.

Bidder's Name

Approved By:

Signature and Title of Bidder



TIMM BORDEN
Deputy Director of Public Works Department

Date

THIS ADDENDUM CONTAINS 7 PAGES

Changes in the Specifications:

Item 1 **DELETE** Section 15-10 on page 26 and **REPLACE** with Section 15-10, to read as follows:

15-10 RELOCATE SIGN, PARKING LIGHTS, AND MODIFICATION OF EX. WORLD OIL SITE – The contractor shall relocate one existing sign, three parking lights, rebuild concrete block planter box, plant new shrubs and sod, install new irrigation system, and modify existing storm drainage system at World Oil site, as shown on the plans. Work shall include demolishing old foundations and construction of new foundation for business sign and new lights.

Cost for removal of plants, existing concrete block planter box, flat grate, irrigation system, business sign and parking lights foundations and other obstructions that are in conflict with the relocation and modification of the existing frontage shall be deemed included in the payment for "Clearing, Grubbing and Removal of Obstruction."

Foundations for the parking lights and sign shall be taken out completely.

Contractor is required to submit a foundation plan for the relocation of the business sign, including the structural calculation, stamped and signed, by a State of California Registered Structural Engineer. Foundation plan will be approved by the City prior to relocation of the existing business sign. Payment for this required shall be deemed included in the payment for this section of work.

Parking light foundation details and the relocation and modifications plans of parking lights will be provided by the City prior to start of construction of the foundations.

Contractor shall coordinate with the World Oil Company representatives prior to commencing any work within their property.

Contractor shall protect and test existing sign and lights before demolition of existing foundation. Temporary storage of existing lights and sign shall be the contractor's responsibility.

Contractor shall also install flat grate inlet and 4" PVC as shown on plans.

Payments to relocate existing sign, parking lights and modification of World Oil site, including concrete foundation for parking lights and sign, foundation plan, and to comply with this section shall include all labor, materials, tools, equipment, and traffic control necessary for doing all of the work as specified herein and as shown on the plans.

This section is provided to account for any unforeseen work not specifically provided for on the Plans or in the Special Provisions. The dollar amount listed below is an estimate only, and will be included in each bidder's proposal. Relocation and modification work shall be performed only upon direct authorization from the Engineer. Contractor shall

submit reports to the Engineer in accordance with the provisions of Section 9-1.03C, "Records," of the Standard Specifications.

This item of work will be measured and paid for as if the work were extra work to be paid for on a force account basis. The provisions of Section 9-1.03, "Force Account Payment," and Section 9-1.03A(1b), "Labor Surcharge," of the Standard Specifications shall apply.

Final payment will be based on the total amount of relocation and modifications actually performed, and will not be subject to the provisions of Section 4-1.03B(1), "Increases of more than 25 percent," of the Standard Specifications.

Payment will be made under:

Relocate Sign, Parking Lights and Modification of Ex. World Oil Site (Revocable)	-	Force Account
---	---	---------------

All bidders shall be required to include in their bids the amount of \$60,000 for this item of work as listed in the Schedule of Quantities.

Item 2 **REPLACE** page 33, under Section 19-2, ROADWAY EXCAVATION, to read as follows:

Additional Excavation (Revocable)	-	Per Cubic Yard
-----------------------------------	---	----------------

World Oil site may contain a small amount of contaminated soil. In such case, additional excavation may be required by the Engineer due to a Class II contaminated soil.

Payment for removing and disposing of Class II contaminated soil shall include full compensation for furnishing all labor, equipment, tools, materials, traffic control, and other incidentals for the work.

Payment will be made under:

Remove and Dispose Class II Contaminated Soil (Revocable)	-	Per Cubic Yard
--	---	----------------

Item 3 **REVISE** fourth paragraph, second sentence under MEDIAN ISLAND INSTALLATION, page 101 to read as follows:

PCC Curb (B1, Median Island)	-	Per Linear Foot
------------------------------	---	-----------------

Item 4 **REPLACE** "Schedule of Quantities for the Senter Road Widening Project Phase II (Tully Road to Singleton Road)" pages 1,2,3,4 of 4 in BID DOCUMENTS and CONTRACT DOCUMENTS with Attachment No. 1.

Schedule of Quantities
for the
Senter Road Widening Project Phase II
(Tully Road to Singleton Road)

Addendum No. 4: Attachment No. 1

Item	Spec. Section	Description	Unit	Quantity	Unit Price	Extension
1	5-2	Street Clean-Up (\$400 Min. per day) (Revocable)	DAY	40		
2	10-2	Storm Water Pollution Prevention	LS	1		
3	11-1	Mobilization (Max. 5% of Total Contract Amount)	LS	1		
4	12-2	Police Officers for Traffic Control (\$45 Minimum per hour per officer, Revocable)	EA	400		
5	12-3	Temporary K-Rail Traffic Control Around PG&E Poles (Revocable)	LF	400		
6	15-3	Additional Potholing (Revocable)	EA	5		
7	15-5	Adjust Water Valve Casing to Grade (Revocable)	EA	16		
8	15-5	Adjust SBWR Water Valve Casing to Grade (Revocable)	EA	14		
9	15-5	Adjust Water Meter Box to Grade (Revocable)	EA	6		
10	15-5	Adjust Pullbox to Grade (Revocable)	EA	2		
11	15-5	Adjust Utility Vault to Grade (Revocable)	EA	2		
12	15-6	Adjust Manhole to Grade (Revocable)	EA	26		
13	15-6	Adjust Monitoring Well to Grade (Revocable)	EA	3		
14	15-6	Adjust SBWR Vault to Grade (Revocable)	EA	2		
15	15-8	Modify Fence and Guardrail Between World Oil and Taqueria	LS	1		
16	15-9	Remove and Replace South Bay Water Air Release Valve and Standpipe	LS	1		
17	15-10	Relocate Sign, Parking Lights and Modification of Ex. World Oil Site (Revocable)	FA	1	\$ 60,000.00	\$ 60,000.00

**Schedule of Quantities
for the
Senter Road Widening Project Phase II
(Tully Road to Singleton Road)**

Addendum No. 4: Attachment No. 1

Item	Spec. Section	Description	Unit	Quantity	Unit Price	Extension
18	15-12	Utility Conflict Work (Revocable)	FA	1	\$ 10,000.00	\$ 10,000.00
19	16-1	Clearing, Grubbing and Removal of Obstructions	LS	1		
20	16-2	Remove & Dispose Metal Pole Siren	EA	1		
21	19-2	Roadway Excavation (Final Pay Quantity)	CY	6,500		
22	19-2	Additional Excavation (Revocable)	CY	500		
23	19-2	Remove Class II Contaminated Soil (Revocable)	CY	400		
24	20-18	Tree - 24" Box	EA	23		
25	20-18	Groundcover - Flats	SF	2,800		
26	20-18	Soil Preparation	SF	4,560		
27	20-18	Decorative Gravel	SF	1,400		
28	20-18	Mulch	SF	2,800		
29	20-18	Moisture Barrier	LF	630		
30	20-18	Imported Topsoil	CY	155		
31	20-18	Decomposed Granite	SF	400		
32	20-18	180 Calendar Day Maintenance Period and Payment of Water Bills	LS	1		
33	20-18	Irrigation System (Including Electrical Work)	LS	1		
34	20-18	Install Water Meter	EA	1		

Schedule of Quantities
for the
Senter Road Widening Project Phase II
(Tully Road to Singleton Road)

Addendum No. 4: Attachment No. 1

Item	Spec. Section	Description	Unit	Quantity	Unit Price	Extension
35	21-1	Class A Subgrade Preparation (Final Pay Quantity)	SF	51,000		
36	39-1	Deeplift AC	TON	4,100		
37	39-1	AC Base Course	TON	1,600		
38	39-1	AC Surface Course	TON	2,000		
39	39-3	Asphalt Concrete Driveway and Walkway Conform (Revocable)	SF	2,000		
40	39-5	Conform Cut	SF	60,000		
41	39-6	Saw Cuts	LF	5,000		
42	73-2	PCC Curb & Gutter (A2) (Include Base)	LF	2,500		
43	73-2	PCC Sidewalk (Include Base)	SF	15,400		
44	73-3	PCC Driveway (Include Base)	SF	1,255		
45	73-3	PCC Wheelchair Ramp w/ Detectable Warning Device (Include Base)	EA	27		
46	73-3	PCC Driveway Curb (Include Base)	LF	90		
47	73-4	PCC Curb (B3-6, Median Island) (Include dowel)	LF	3,400		
48	73-4	PCC Curb (B1, Median Island)	LF	2,100		
49	73-4	6" PCC in Median Island	SF	630		
50	73-4	4"-8" dia. Cobblestone with 6" Concrete Mortar Bed	SF	4,730		
51	73-6	Truncated Domes (Revocable)	SF	200		

Schedule of Quantities
for the
Senter Road Widening Project Phase II
(Tully Road to Singleton Road)

Addendum No. 4: Attachment No. 1

Item	Spec. Section	Description	Unit	Quantity	Unit Price	Extension
52	81-2	Adjust Survey Monument box to grade	EA	2		
53	84-1	Remove and Restrip Traffic Stripes & Pavement Markings	LS	1		
54	86-2.05C.6	Additional 1 1/2" Conduit (In Place) (Revocable)	LF	30		
55	86-2.06.3	Additional #3 1/2 Pull Box (In Place) (Revocable)	EA	2		
56	86-9.1	Street Lighting	LS	1		
57	86-9.1B	Additional 10B Street Light Pole with 8 Foot Luminaire Arm, 180 W LPS Luminaire, Foundation, and #3 1/2 Pull Box (In Place) (Revocable)	LS	1		
58	86-9.2	Traffic Signal Modification at Senter Rd. & Umbarger Rd.	LS	1		
59	86-9.2	Traffic Signal Modification at Senter Rd. & Southside Rd.	LS	1		
60	86-9.2	Traffic Signal Modification at Capitol Expwy. & Senter Rd.	LS	1		
61	1301-2	Trench Sheet piling, Shoring and Bracing (Revocable)	LS	1		
62	1302-3	12-inch Dia. RCP, Class V, Neoprene Rubber Gasket (Revocable)	LF	57		
63	1305-1	Standard Storm Manhole	EA	1		
64	1305-1	Regular Hooded Inlet	EA	5		
					TOTAL	